



Federal Institute for Materials Research and Testing

X-ray endoscopy for inspection of tube to tube sheet welds in heat exchangers

18th WCNDT Durban, South Africa, 2012

U. Zscherpel, U. Ewert / BAM Berlin, Germany

P. Rost, M. Schmid / BASF SE, Germany


K. Spartiotis / Oy AJAT, Finland

A. Warrikhoff / RTW X-ray, Germany



Tasks of heat exchangers NDT of tube sheet welds

- Heat exchangers are central components in chemical processing industries
- Heat transfer from medium 1 to medium 2 without direct contact
- Considered here: tube bundle heat exchangers
- Leak-thightness of tube-to-tube sheet connection essential for safety and availability of chemical plants




- <u>Minor problem</u>: No standards for NDT of tube-to-tube sheet connections available
- But: Considerable increase of application in a global scale!

Tube - to - tube sheet connection (TTS) Inspection task




Aim of inspection:

Imaging of TTS weldment by one exposure with sufficient image quality and flaw visibility



:

The Chemical Company



Solution:

- gamma- or X-ray source
- application of wall thickness compensators
- suitable detector focus distance depending on diameter and wall thickness of the pipes

NDT for inspection of TTS welds History


Federal Institute for Materials Research and Testing


The Chemical Company

BASE

- Introduction of gamma container with Isotopic source Ir-192 (1.0 x 0.5 mm²) in 1975
- Successfully application at the manufacturing site of the heat exchangers on request of chemical industry **until today** (film based)
- Constantly ca. 100 200 inspections per year by BASF only
- Influence on weld quality by NDT directly during manufacturing process at the manufacturing site
- Visibility of single pores starting from 0.5 mm diameter
- Acceptance criteria in written practice of BASF

Continuous reports on inspections at conferences, working groups and committees of the German NDT society, e.g. by BAYER and BASF





NDT for inspection of TTS welds Why a new inspection system?

Facts:

- Inspection continuosly important for safe operation of heat exchangers
- Transport of radiactive containers requires more organizational efforts
- Usage and transport of isotopes on international scale nearly impossible

Aims:

- Increase mobility for BASF worldwide
- Reduce radiation exposure
- Inspection of different materials (Fe, Ti, Ni, …)
- Reduction of costs:
 - ommision of consumables like films and chemistry ("greener world")
 - constant and short exposure times
- Immediate evaluation of results on-site, therefore important contribution to process optimization

Step 1: **Development of rod anode X-ray tube**

rtw RÖNTGEN-TECHNIK DR. WARRIKHOFF GmbH & Co. KG



BASE

The Chemical Company





6

Step 2: Developement of digital detector array

- direct converting detector CdTe CMOS
- 4 active tiles around rod anode
- pixel size 100 µm x 100 µm
- X-ray voltage 40 130 kV
- exposure time 10 30 s
- Image acquisition 20 frames/s
- inspection of Pipe- Ø 20 30 mm
- porosity detectable > Ø 0,2 mm



Bundesanstalt für Materialforschung und -prüfung





The Chemical Company

55

Control of X-ray tube and Image Evaluation by Isee! image acquisition & storage: 🔞 ISee! : \\Trappist\data\alex\develop ent\ppji\data\20060628-\pipe32-75kV-0.3mA-cal4-2 - IX File View Image Mode Misc ¹√³ St³ ⁸A⁶ A⁷ −R +R +C 約 闰 1:1 史 Q !! 🖬 🗒 🖉 Description Value 32nix D Roi1 🖳 📢 🏷 😘 St 🗛 🗛 📗 -R +R Boi2 28pix D 26pix D Roi3 Roi4 26pix D Roi5 24pix D Roi6 22pix D Roi7 22pix D 🚼 Pipe-Plate-Joir _ 🗆 🗙 File Mode Show Project Base: ist\data\alex\development\ppji\data\20061106-BASF-SchwarzHeide ... Control X-Ray Source X-Ray Tube Voltage: 90 kΥ X-Ray Tube Current: 0.2 mA Camera calibration: C:\Dokumente und Einstellungen\alex\Eigene Dateien\devel ... Calibration temperature: 23,4 *C Actual camera temperature: 24.3 °C Dark current drift compensation: Measure DC ✓ Automatic 5.0 sec Integration: Bottom Row Pipe Variant Aa Ab 2013 W 500 Ok Comment Image display, image • Row: 4 Pipe: 6 Variant: try2 Bottom: 1 Start processing, indication sizing Show Filter Findings □ 2011/Aa □ 2016/Ab □ 2013 □ 500 □ W Fulfiled Comment Delete New 141% (545.550): 32759

Step 3: Developement of software / user interface

BAM software for digital radiology, image processing and image analysis:

Bundesanstalt für

Materialforschung

und -prüfung

The Chemical Company

lsee!

http://dir.bam.de/ic

NDT for inspection of TTS welds Chronology of inspection techniques

BASF The Chemical Company

Isotope Ir-192 NDT film based



Advantages:

- large wall thickness range
- easy applicable

Disadvantages:

- permanent radiation source
- radioactive container
- limited detail visibility
- low efficiency with DDAs

X-ray tube NDT film based



Advantages:

- high detail visibility
- fixed exposure parameters
- easy transport

Disadvantages:

- lower wallthickness range
- electricity on-site required

X-ray tube DDA based



Advantages:

- see X-ray tube
- lower radiation exposure
- immediately evaluation
- no consumables

Disadvantages:

- mechanically sensible system (connectors!)
- high investment costs

New TTS inspection system Contribution of BASF (practical validation)

- Verification of detection sensitivity by
 - test plates
 - modular reference blocks
 - real heat exchangers
- Investigation of influencing parameters
 - X-ray voltage, exposure time, image processing
 - pipe diameters, wall thicknesses, materials
 - Stability in practice on-site



- Transfer of practical experiences to the TTS inspection system
 - design changes at rod anode and digital detector (heat distribution)
 - modified instructions for radiation protection
 - modified procedure for image evaluation and indication assessment by trained operators (validated acceptance criteria)


New TTS inspection system Verification of inspection sensitivity


Federal Institute for Materials Research and Testing

The Chemical Company

BASF

Test plate with TTS







detector image Ø25 x 2 mm

New TTS inspection system Comparison with test plate, pipe 25x2 mm²












The Chemical Company



85 GBq, 1 x 0.5 mm², C3 film, 2 x 0,02 Pb screens $t_e = 1 min$



130 kV, 0.5 mA, C3 film, 1 mm Sn filter, 2 x 0,02 Pb $t_e = 0.5 min$




75 kV, 0.5 mA, $t_e = 10 s$ digital high pass filter

New TTS inspection system Further comparisons




The Chemical Company




Gamma exposure with Isotope Ir-192 , film based

High wall thickness range: evaluation of pipes in neighbourhood possible




X-ray exposure 130 kV / 0.5 mA / 30 s film based

X-ray exposure with digital detector array 75 kV / 0.5 mA / 10 s



New TTS inspection system Exposures with X-ray tube and DDA

Influence of **exposure time** on image quality




without image processing

30 s 10 s

1 s

The Chemical Company



using image processing ("Extract Details" in Isee!)

exposure parameters: \emptyset 25 x 2 mm – **75 kV /** 0.5 mA / SDD = 37mm

New TTS inspection system Exposures at TTS 20 mm x 2 mm

 Ø1 x 0,75 mm
 Ø 0,25 x 0,25 mm

 Ø1 x 0,25 mm
 Ø 0,25 x 0,75 mm


 Ø 0,25 x 0,75 mm
 Ø 0,25 x 0,75 mm

 Ø 0,7 x 0,75 mm
 Ø 0,5 x 0,25 mm

 Ø 0,7 x 0,25 mm
 Ø 0,5 x 0,25 mm

 Ø 0,7 x 0,25 mm
 Ø 0,5 x 0,25 mm

Detector exposure: **70 kV** /0.5 mA / 30 s





Detector exposure: **85 kV** /0.5 mA / 30 s

BASF


New TTS inspection system Practical examples


Federal Institute for Materials Research and Testing














New TTS inspection system


Error sources

Important: Positioning and exact fitting of parts of equipment

- Therefore:
 - application of suitable wall compensation pieces
 - correct exposure parameters and image processing
 - exact alignment of inspection unit relative to tube sheet plate



Inspection unit aligned



Inspection unit not aligned



Important image information is lost at improper alignment of the inspection unit, even when the correct exposure parameters have been used!



New TTS inspection system Radiation protection



The Chemical Company

3 =



Dose rate at 0.5 m

behind X-ray tube

kV	mA	S	µSv/h
70	0,5	30	0,4
75	0,5	30	2
80	0,5	30	5
85	0,5	30	18
90	0,5	30	60

Advantages:

- Lower radiation exposure for inspection personnel
- Restricted access area smaller than 2x2 m²
- No influence of production processes at the manufacturing site



New TTS inspection system Detail visibility


Radiographic inspection of TTS:

Gamma radiation (Ir-192)

back radiation technique ($d=1x0,5 \text{ mm}^2$) or penetration technique ($d=2x1 \text{ mm}^2$)

- X-ray tube + film (rod anode tube, d = 0.6 mm), back radiation technique with filmsystem C3
- X-ray tube + detector

 (rod anode tube, d = 0.6 mm)
 back radiation technique mit CdTe detector



9-

20

New TTS inspection system Summary - Advantages

- No transportation of dangerous goods
- Global applicability
- Reduced exposure times
- Radiation protection:
 - Small controlled area at 75 kV
 - No disturbance of production processes at manufacturing site
- Visual defect assessment (image processing / defect sizing)
- Improved defect detection
- No consumables (cost reduction)
- Process optimization by onsite evaluation





New TTS inspection system



The Chemical Company

SE

Excellent co-operation between:



Peter Rost, Markus Schmid and Team







Alexander Warrikhoff and Team

Prof. Uwe Ewert , Dr. Uwe Zscherpel, Dr. Oleksandr Alekseychuk

Dr. Konstantinos Spartiotis and Team

